

SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC -5 AM 9:00

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>6N</u> R <u>11W</u> | <u>L-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

William R. Byl
REG. OF DEEDS

7704

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on July 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|-----|------|---------------|-----------|--------------------------|
| L-3 | 1831 | GLO | Mullett | Set Post |
| | 1973 | Kent Co. Wit. | | Iron & Stone |
| | 1981 | LCRC #430 | VanKooten | 3/4" Iron |
| | 1989 | LCRC #2038 | Hackbardt | Set Kent County Monument |
| | | LCRC #4975 | Bueche | Kent County Monument |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/1/94
CHAIRMAN *Harry Thacker*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 7/14/81 and was recorded per LCRC #2038

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Glen S. Hackbardt in place of the 3/4" Iron he found. Said Iron checks with LCRC #430.

LCRC #2038		LCRC #4975	
C/L hydrant	N50°W 51.10'	C/L hydrant	N50°W 51.10'
C/L manhole	N55°W 35.02'	Nail & Remon. tag S. side Lt. Pole	S85°E 21.15'
1/2" x 18" rebar	South 50.00'	Nail & Remon. tag S. side Serv. Pole	N90°W 24.15'
1/2" x 18" rebar	North 50.00'	Nail & Remon. tag top guard rail post	N20°W 55.07'
Nail & tag Lt. Pole	S85°E 21.15'	Nail & Remon. tag top guard rail post	S25°E 46.90'
		C/L blacktop N-S	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|-------|--------|
| L-3 Standard Kent County Monument | | |
| C/L hydrant | N50°W | 51.10' |
| Nail & KC Remon. tag S. side Lt. Pole | S85°E | 21.15' |
| Nail & KC Remon. tag S. side Serv. Pole | N90°W | 24.15' |
| Nail & KC Remon. tag top guard rail post | N20°W | 55.07' |
| Nail & KC Remon. tag top guard rail post | S25°E | 46.90' |
| C/L blacktop N-S | | |



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 112794