SURVEY & MONUMENTATION

KENT COUNTY REMONUMENTATION

$7.00
$2.00

JAN 2 4 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 DEC 20 AM 8: 39
REG. OF DEEDS
8808
Register of Deeds Stamp & File Number

	Located In:	Corner Code #
1. Public Land Survey	T 6N R 11W	L-6
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling	S ___ T ___ R ___	
in Section	S ___ T ___ R ___	
3. Miscellaneous	S ___ T ___ R ___	
Property in Section	S ___ T ___ R ___	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



I, Kirk Breitels, in a field survey on Nov. 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-6 1831 GLO — Not Set
1956-86 Williams & Works — Set-used "T" Iron at "X" 1/4 lines
1983 LCRC #3623 Meyer — Reset "T" Iron at intersection of 1/4 lines
10" Poplar N. 9.41' Tw. 6" Elm N35°W 24.10'
8" wood fence post E. 61.4' C/L MH S45°E 9.45' Iron 1' S. & 1.3' W.
Exxel Eng. — Used computed "X" 1/4 lines

B. *Description of corner evidence found and/or method applied in restoring or reestablishing corner:*

L-6 Found "T" Iron that fits remaining witnesses of those above. Said "T" Iron is 0.1' N. & 0.3' E. from true intersection of 1/4 lines.

The "T" Iron is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 647 1997 KENT COUNTY
PLER APPROVED 12/1/97
CHAIRMAN Gary Huber

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-6 Set Standard Kent County Monument in place of the "T" Iron.
C/L sewer manhole — S25°E 9.40'
Set Nail & KC Remon. tag S. side 12" Poplar — S90°W 72.25'
Set Nail & KC Remon. tag E. side 8" Willow — N10°W 58.25'
Set Nail & KC Remon. tag N. side 15" Ash — N80°E 79.42'
C/L foot path is East 10'±
C/L stream running E-W is North 70'±

STATE OF MICHIGAN
KIRK BREITELS
LAND SURVEYOR
NO 30077
LICENSED LAND SURVEYOR

Signed by Kirk Breitels Date 12/11/95

Surveyor's Michigan License No. 30077

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983