

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -5 AM 9:00

W. R. Byl
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T <u>6N</u> R <u>11W</u>	<u>L-9</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

7707
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on Sept. 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9	1831	GLO	Mullett	Set Post
	1963	Kent Co. Wit.		3/4" Iron
	1973	LCRC #433	VanKooten	3/4" Iron
	1981	LCRC #2039	Hackbardt	Set Kent County Monument
	1984	LCRC #3953	Bonnema	Reset Kent County Monument
	1989	LCRC #4978	Bueche	Kent County Monument
	1993	LCRC #6751	Roon	Kent County Monument

P.A. 74
PEER APPROVED 12/1/94
CHAIRMAN *Harry Debus*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 7/6/81 and was recorded per LCRC #2039

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
L-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in the same position as set in 1981 by Glen S. Hackbardt in place of the 1" x 18" Iron he found inside a mon. box. Said Iron in mon. box checks with Kent Co. Wit. and LCRC #433.

LCRC #3953		LCRC #6751	
C/L SW bolt RR flasher	N17°W 44.45'	Chiseled "X" on MH rim	West 51.12'
C/L NW bolt RR flasher	S43°W 56.42'	NE bolt RR flasher base	S55°W 55.44'
E. edge E. rail	West 23.14'	SW bolt RR flasher base	N17°W 44.40'
SE cor. brick bldg.	N47°W 168.61'	Nail & tag P. Pole	South 44.14'
Nail & tag P. Pole	S66°W 95.28'		
SE cor. brick wing	N33°W 138.89'		
SW cor. brick wing	N14°E 120.56'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Standard Kent County Monument in C/L 20' traffic median	
E. edge E. rail of N-S track	S90°W 23.11'
SE cor. brick bldg.	N47°W 168.61'
Nail & KC Remon. tag NW side P. Pole	S66°W 95.28'
SE cor. brick wing on S. side bldg.	N33°E 138.83'
SW cor. brick wing on S. side bldg.	N14°E 120.47'
Chiseled "X" on E. side MH rim	S90°W 51.12'
NE bolt RR flasher base	S55°W 55.44'
SW bolt RR flasher base	N17°W 44.40'
Nail & MDSH tag E. side P. Pole	S00°E 44.14'

Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 12794

