

**SURVEY & REMONUMENTATION**

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC -5 AM 9:00

For corners in  
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 11W	L-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Lucy Bond*  
REG. OF DEEDS

7708

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-11	1831	GLO	Mullett	Set Post
	1972	LCRC #174	Spicer	1/2" Iron in mon. box
	1982	LCRC #3131	Bonnema	Set Kent County Monument
	1989	LCRC #4979	Bueche	Kent County Monument
	1993	LCRC #6751	Roon	Kent County Monument
	1993	LCRC #6782	Brintnall	Reset Kent Co. Mon. after const.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 8/9/82 and was recorded per LCRC #3131

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Arthur W. Brintnall in the same position as set in 1982 by Douglas W. Bonnema over the 3/4" Iron he found in blacktop road 30" deep. Said Iron checks with LCRC #174 and survey data of others.

LCRC #3131		LCRC #6782	
Nail & tag 8" Poplar	S43°E 92.56'	N45°W 139.32'	SE bolt Lt. Pole base
PK & tag P. Pole	S17°W 32.04'	N00°W 63.48'	Nail & tag E. side 10" Elm
PK & tag N. edge gutter	S51°W 36.44'	S15°E 47.57'	Nail & tag E. side P. Pole
Nail & tag 6" Ash	N42°W 45.23'	S07°W 187.56'	Nail & tag E. side 8" Pine
C/L top of hydrant	North 26.43'	S35°E 34.05'	SE cor. back CB
Nail & tag 15" Hickory	N64°E 65.71'	N35°W 34.29'	NE cor. back CB
		S55°W 194.44'	PK & tag top C&G

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Standard Kent County Monument	
SE bolt Lt. Pole base	N45°W 139.32'
New Nail & KC Remon. tag E. side 10" Elm	N00°W 63.48'
New Nail & KC Remon. tag E. side P. Pole	S15°E 47.63'
New Nail & KC Remon. tag E. side 8" Pine	S07°W 187.40'
SE cor. back CB	S35°E 34.07'
NE cor. back CB	N35°W 34.29'
"V" cut in conc. base of flag pole	S50°W 146.90'

Signed by *William R. Byl*  
Surveyor's Michigan License No. 23502

Date 112794

