

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94
DEC -5 AM 9:00

William R. Byl
REG. OF DEEDS

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	L-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

7709

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl in a field survey on July 7, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the Michigan Board of Land Surveyors or by a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13	1831	GLO	Mullett	Set Post
	1954	Kent Co. Wit.		Iron in C/L B.T.
	1983	LCRC #3222	Bonnema	Pinched Iron Pipe on C/L
	1983	LCRC #3483	Byl	Set Kent County Monument
	1989	LCRC #4980	Bueche	Kent County Monument
	1993	LCRC #6761	Roon	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/1/94
CHAIRMAN *Harry Stude*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 7/21/83 and was recorded per LCRC #3483

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the Pinched Iron Pipe he found. Said Pinched Iron Pipe checks with Kent Co. Wit. and LCRC #3222.

LCRC #3483	LCRC #6761
Nail & tag 18" Quad. Maple S10°W 37.36'	KC Mon. (L-1, T5N, R11W) East 13.55'
Nail & tag 18" Oak S75°W 66.57'	Nail & tag P. Pole North 54.62'
Nail & tag 4" Ash clump N65°W 54.61'	Nail & tag 18" Maple Clump N60°W 61.73'
Nail & tag P. Pole N05°E 61.63'	Nail & tag 26" Maple S15°W 27.35'
N 1/4 cor. Sec. 1, 5-11 (Kent Co. Mon.) East 13.57'	Nail & tag 9" Ash S45°W 30.99'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Standard Kent County Monument	
Kent Co. Mon. (L-1, T5N, R11W)	S90°E 13.55'
Nail & KC Remon. tag NE side P. Pole	N00°E 54.60'
New Nail & KC Remon. tag S. side 18" Ash Clump	N60°W 61.76'
New Nail & KC Remon. tag E. side 26" Maple	S15°W 27.37'
New Nail & KC Remon. tag SE side 9" Ash	S45°W 31.02'
New Nail & KC Remon. tag SW side 8" Oak	S50°E 38.60'

Signed by

William R. Byl

Date

112794

Surveyor's Michigan License No.

23502

