

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -5 AM 9:01

COMMISSION

For corners in
KENT COUNTY

W. R. Byl
REG. OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7711

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corners mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2	1831	GLO	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	1964	Kent Co. Wit.		Iron	PEER APPROVED 12/1/94
	1979	LCRC #1302		1" Iron	CHAIRMAN <i>Harry Hutten</i>
	1981	LCRC #2167	Jonker	Set Kent County Monument	
	1989	LCRC #4981	Bueche	Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/25/81 and was recorded per LCRC #2167

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #1302.

LCRC #2167	LCRC #4981
Remon. tag 28" Oak	S37°E 29.70'
Remon. tag 16" Hickory	N87°W 56.50'
Remon. tag 14" Maple	N70°E 21.49'
Iron North 82.48'	Nail & tag NE side 36" Oak
At corner of old fences W-N-S	Nail & tag N. side 20" Hickory
	Nail & tag NW side 16" Maple
	Nail & tag W. side 20" Oak
	Nail & tag E. side 8" Maple
	KC Mon. (A-2, T6N, R10W)
	North 82.48'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Standard Kent County Monument	
New Nail & KC Remon. tag NE side 36" Oak	S37°E 29.68'
New Nail & KC Remon. tag N. side 20" Hickory	N87°W 56.40'
New Nail & KC Remon. tag NW side 16" Maple	N70°E 21.86'
New Nail & KC Remon. tag W. side 20" Oak	N05°W 28.01'
New Nail & KC Remon. tag E. side 8" Maple	S10°W 18.81'
Kent Co. Mon. (A-2, T6N, R10W)	N00°E 82.50'

Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 112794

