

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC -5 AM 9:01

Lucy Bond
REG. OF DEEDS

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 11W	M-4
	T R	
	T R	
	T R	
	T R	<i>Seg. #1</i>
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

7712

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on July 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-4	1831	GLO	Mullett	Set Post
	1959	Kent Co. Wit.		1" Bolt
	1972	LCRC #342	Spicer	PK Nail
	1981	LCRC #2163	Jonker	Set Kent County Monument
	1989	LCRC #4983	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED *12/11/94*
CHAIRMAN *Harry Spuhler*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/26/81 and was recorded per LCRC #2163

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Solid Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #342.

LCRC #2163	LCRC #4983
MSHD tag NW side P. Pole	N43°E 79.52'
MSHD tag SW side P. Pole	N53°W 48.55'
Nail & Remon. tag N. side P. Pole	S72°W 69.93'
Nail & Remon. tag N. side P. Pole	S61°E 58.80'
C/L Manhole	S72°W 18.35'
Kent Co. Mon.	South 7.15'
C/L "X" B.T. os 3' N. & 2' W.	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Standard Kent County Monument	
Nail & MSHD tag NW side P. Pole	N43°E 79.52'
Set Nail & KC Remon. tag SW side P. Pole	N53°W 48.49'
Nail & KC Remon. tag N. side P. Pole	S72°W 69.91'
Nail & KC Remon. tag N. side P. Pole	S61°E 58.88'
C/L Manhole	S72°W 18.35'
Kent Co. Mon. (A-4, T6N, R10W)	S00°E 7.15'
C/L "X" B.T. os 3' N. & 2' W.	

Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 112794

