

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

94 DEC -5 AM 9:01

Lee J. Bond
 REG. OF DEEDS

For corners in
KENT COUNTY

(County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

7713

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on Sept. 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		3/4" Iron in mon. box
	1972	LCRC #147	Jones	1" Iron in mon. box
	1972	LCRC #342	Spicer	3/4" Iron in mon. box
	1981	LCRC #2145	Jonker	Set Kent County Monument in mon. box
	1989	LCRC #4984	Bueche	Kent County Monument in mon. box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9/1/81 and was recorded per LCRC #2145

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/1/94
 CHAIRMAN *Henry Hudson*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Solid Iron he found inside a mon. box. Said Iron in mon. box checks with Kent Co. Wit. and LCRC's #147 & #342.

LCRC #2145			LCRC #4984		
Remon. tag P. Pole	S62°E	121.8'	Nail & Remon. tag N. side P. Pole	S62°E	121.8'
Remon. tag P. Pole	N29°W	62.25'	Nail & Remon. tag W. side Lt. Pole	N37°E	80.80'
Remon. tag L. Pole	N37°E	80.80'	Nail & Remon. tag NE side P. Pole	N45°W	78.95'
SE cor. back CB	S58°W	81.97'	SE cor. back of CB	S50°W	84.00'
Mon. box South	10.5' m/1		KC Mon. in mon. box (A-5 T6N, R10W)	South	10.48'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Standard Kent County Monument in mon. box		
Nail & KC Remon. tag N. side P. Pole	S62°E	121.98
SE cor. back of CB	S50°W	85.85'
C/L top hydrant	S60°W	113.67'
Set Nail & KC Remon. tag E. side P. Pole	N35°E	85.96'
Set Nail & KC Remon. tag NE side P. Pole	N45°W	101.25'
NE cor. CB header	N55°W	92.34'
KC Mon. in mon. box (A-5 T6N, R10W)	S00°E	10.53'

Signed by *W. R. Byl*
 Surveyor's Michigan License No. 23502

Date 112794

