

SURVEY & REMONUMENTATION

APR 27 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC -5 AM 9:01

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>11W</u>	M-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

W. J. Bond
REG. OF DEEDS

7714

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on Oct. 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-6 1831 GLO Mullett Set Post
1983 LCRC #3623 Stadt Set PK & tag on Twp. line 5.35' N. of W 1/4 cor. Sec. 18-6-10 as held by previous surveys.
1984 LCRC #3866 Rosema Set Kent County Monument
1988 LCRC #4897 Bueche Reset Kent Co. Mon. after road const.
1989 LCRC #4985 Bueche Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 8/4/84 and was recorded per LCRC #3866

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche at the same position as set in 1984 by Maurice J. Rosema in place of the PK Nail & tag he found. Said PK Nail & tag checks with LCRC #3623.

LCRC #4897	LCRC #4985
Nail & Remon. tag N. side 15" Basswood	S87°E 105.06'
C/L top of hydrant	N10°W 188.12'
PK Nail & Remon. tag NE side P. Pole	S24°E 98.88'
"X" cut in conc. curb	N48°W 46.90'
"X" cut in conc. curb	S42°W 57.65'
KC Mon. (A-6, Cascade Twp.)	South 5.41'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-6 Standard Kent County Monument
Nail & KC Remon. tag N. side 18" Basswood S87°E 105.04'
C/L top of hydrant N10°W 188.00'
PK Nail & Remon. tag NE side P. Pole S24°E 98.95'
NW cor. CB header S25°W 94.96'
SE cor. CB header N10°E 149.54'
KC Mon. (A-6, Cascade Twp.) S00°E 5.44'

Signed by William R. Byl
Surveyor's Michigan License No. 23502

Date 11/27/94
CHAIRMAN Harvey Huber
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 (REVISED MAY 14, 1975 REVISED JAN., 1983)

