

SEP 18 1995
\$7.00
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 MAY 12 AM 10:43

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

W. J. Bond
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 6N R 11W	M-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

8355
Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on March 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10	1831	GLO	Mullett	Set Post
	1972	LCRC #201	Spicer	1/2" Iron in mon. box
	1972	LCRC #274	VanKooten	1" Iron in mon. box
	1981	LCRC #2161	Jonker	Set Kent Co. Mon. in mon. box
	1989	LCRC #4989	Bueche	Kent Co. Mon. in mon. box
	1993	LCRC #6752	Roon	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9/1/81 and was recorded per LCRC # 2161

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found PK Nail (road const. 1994) at the same location as Kent Co. Mon. as set in 1981 by Robert J. Jonker in place of the 3/4" Round Iron he found inside a mon. box. Said Iron in mon. box fit LCRC's #201 & #274. Said PK Nail fits previous survey data prior to construction and remaining witnesses of LCRC's #2161, #4989, #6752. Found remains of Kent Co. Mon. 24" below road grade.

LCRC #2161 & #4989

C/L Hydr.	N55°W	33.65'
KC Mon.	N	5.63'
NW cor. conc. to util. ped.	S47°E	60.7'
Face of South gate post	S66°W	67.6'

On C/L N-S B.T.

P.A. 345 1990 KENT COUNTY,
PEER APPROVED 3/30/95
CHAIRMAN Harrison Huber

The selected position is accepted by me and is generally accepted by professional surveyors as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Set Standard Kent County Monument (Harrison) in place of the PK Nail over remains of original Kent Co. Mon.

Top C/L Fire Hydrant	N55°W	44.68'
KC Mon. (A-10, T6N, R10W)	N00°E	5.64'
NW cor. Elec. Box (4' High)	S50°E	55.77'
Face of South gate post	S80°W	56.30'
Face of North gate post	N85°W	54.91'

On C/L N-S B.T.



Signed by Kirk Breitels Date 3/30/95
Surveyor's Michigan License No. 30077