

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION.

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

- | | | | | | |
|--------------------------------------|---|----|---|-----|---------|
| 1. Public Land Survey | T | 6N | R | 11W | M-4 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | Seg. #2 |
| | S | | T | | |
| 3. Miscellaneous Property in Section | S | | T | | |
| | S | | T | | |

REG. OF DEEDS

Lucy St. John

96 SEP 13 PM 12:03

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9339

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **Kirk Breitels**, in a field survey on **July 29**, 19**96**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|-----|------|---------------|---------|--------------------------|
| M-4 | 1831 | GLO | Mullett | Set Post |
| | 1959 | Kent Co. Wit. | | 1" Bolt |
| | 1972 | LCRC #342 | Spicer | PK Nail |
| | 1981 | LCRC #2163 | Jonker | Set Kent County Monument |
| | 1989 | LCRC #4983 | Bueche | Kent County Monument |
| | 1994 | LCRC #7712 | Byl | Kent County Monument |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/22/96
CHAIRMAN Hans Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/26/81 and was recorded per LCRC #2163

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 Found NOTHING AT CORNER. Set Standard Kent Co. Mon. (Harrison) at same location per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Solid Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #342.

LCRC #2163 & #4983 & #7712

- | | | |
|-----------------------------------|-------|--------|
| MSHD tag NW side P. Pole | N43°E | 79.52' |
| MSHD tag SW side P. Pole | N53°W | 48.55' |
| Nail & Remon. tag N. side P. Pole | S72°W | 69.93' |
| Nail & Remon. tag N. side P. Pole | S61°E | 58.80' |
| C/L Manhole | S72°W | 18.35' |
| Kent Co. Mon. | South | 7.15' |
- C/L "X" B.T. is 3' N. & 2' W.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-4 Standard Kent County Monument
- | | | |
|---------------------------------|-------|---------|
| NE corner CB header | S40°E | 52.76' |
| NW corner CB header | S35°W | 51.54' |
| NW corner brick house | S60°W | 153.42' |
| NW corner CB header | N60°W | 54.32' |
| Nail & MDSH tag NW side P. Pole | N43°E | 79.50' |
| C/L Manhole | S72°W | 18.26' |
| Kent Co. Mon. (A-4, T6N, R10W) | South | 7.16' |



Signed by *Kirk Breitels*

Date 8/25/96

Surveyor's Michigan License No. 30077