

SURVEY & REMONUMENTATION

APR 28 1995

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 29 AM 9:17

For corners in
Kent

Located In:

Corner Code #

1. Public Land Survey	T 6N R 12W	A-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Tim J. Bond
REG. OF DEEDS

7388

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on March 31, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3	1831	G.L.O. Notes	L. Lyon	Set Post
	??	Wit. Map	K.C. Surveyor	Iron & Tile
	1972	L.C.R.C. #202	Williams & Works	Iron
	1980	L.C.R.C. #1445	Williams & Works	Iron & Tile/Set K.C. Monument
	1990	L.C.R.C. #5697	Milliton	K.C. Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by Williams & Works, Inc., on 10/24/80 and was recorded per L.C.R.C. #1445

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3 Found K.C. Monument in C/L of Kenowa Avenue running N-S on C/L Burton Street running East as set by Williams & Works in place of a "T" iron over a 1/2" iron over a 3/4" iron in a 4" tile using K.C. Surveyors wits. and L.C.R.C. #202.

L.C.R.C. #5697

- Nail & K.C. remon. tag E side 24" Maple N 30° W 45.78'
- Nail & K.C. remon. tag E side Hackberry N 20° W 87.31'
- Nail & K.C. remon. tag NW side 20" Hickory N 15° E 94.88'
- Nail & K.C. remon. tag SW side p. pole N 60° E 41.49'
- Nail SW side 42" Sycamore S 40° E 75.15'
- Nail & K.C. remon. tag W side 16" Pine S 40° W 55.56'

P.A. 345 1990 KENT COUNTY


PEER APPROVED 8/11/94

CHAIRMAN Harry Huber

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3	Standard Kent County Monument
	Nail & K.C. remon. tag E side 24" Maple N 30° W 45.78'
	Nail & K.C. remon. tag E side Hackberry N 20° W 87.31'
	Nail & K.C. remon. tag NW side 20" Hickory N 15° E 94.88'
	Nail & K.C. remon. tag SW side p. pole N 60° E 41.49'
	Nail & K.C. remon. tag W side 16" Pine S 40° W 55.56'
	Nail SW side 42" Sycamore S 40° E 75.89'



Signed by Randy J. Kolehouse
Surveyor's Michigan License No. 25854

Date 11/21/94