

# SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 29 AM 9:17

For corners in Kent **COMMISSION**  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. J. Bond*  
REG. OF DEEDS

7395

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on March 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-10 This corner was not originally set by the G.L.O.

1945 Williams & Works Records	Iron
1966 MDOT	Iron
1975 L.C.R.C. 807	Mon. Box
1984 L.C.R.C. 3933	McCloskey Rosema Set K.C. Monument.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Maurice J. Rosema and was recorded per L.C.R.C. #3933.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-10 Found standard Kent County Monument (Harrison) in the center line of Kenowa Ave. (running North & South) per witness from L.C.R.C. #3933 as set by Maurice Rosema in place of an iron with brass cap in a monument box which he found to check the County Surveyor's records (1943) and MDOT records.

L.C.R.C. #3933

PK nail & K.C. remon. tag in N side guard rail post S 73° E 24.19'  
C/L NW bolt at N end steel bridge rail on E side of road S 26° E 50.27'  
C/L NE bolt at N end steel bridge rail on W side of road S 14° W 89.54'  
PK nail & K.C. remon. tag in S side guard rail post N 58° W 28.39'  
Iron in mon. box (M-10, T6N, R13W) - N 13.80'


P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/28/94  
CHAIRMAN *Randy Kolehouse*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-10 Standard Kent County Monument

PK nail & K.C. remon. tag in N side guard rail post S 73° E 24.19'  
C/L NW bolt at N end steel bridge rail on E side of road S 26° E 50.27'  
C/L NE bolt at N end steel bridge rail on W side of road S 14° W 89.54'  
PK nail & K.C. remon. tag in S side guard rail post N 58° W 28.39'  
Iron in mon. box (M-10, T6N, R13W) - N 13.80'



Signed by *Randy J. Kolehouse*  
Surveyor's Michigan License No. 25854

Date 11/21/94