

**SURVEY & REMONUMENTATION**

Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 29 AM 9:17

For corners in **COMMISSION**  
Kent  
(County)

Located In: Corner Code #

*Lee J. Bond*  
REG. OF DEEDS

1. Public Land Survey	T 6N R 12W	A-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

7397

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on March 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-12 This corner was not originally set by the G.L.O.

1944	Wit. Map	K.C. Surveyor	3/4" Iron
1973	L.C.R.C. #438	Medema, Van Kooten, Inc.	1/2" Iron
1982	L.C.R.C. #3175	Rob Jonker	Found 3/4" Iron/Set K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Jonker Land Surveys on 12/17/82 and was recorded per L.C.R.C. #3175.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12 Found K.C. Monument per L.C.R.C. #3175 in C/L Kenowa Avenue running N-S and 56th Street running East as set by Rob Jonker in place of a 3/4" iron he found using K.C. Surveyors wits. and L.C.R.C. #438.

L.C.R.C. #3175

- Nail & K.C. remon. tag on SE side p. pole S 45° W 50.91'
- Nail & K.C. remon. tag on NW side p. pole N 45° E 51.59'
- NW corner house fnd. S 45° E 84.40'
- C/L water valve N 25° W 33.48'
- On C/L to N, W, S, C/L to E is N 5' m/l

P.A. 345 1990 KENT COUNTY

PEER APPROVED

CHIEF MAN


*7/28/94*  
*Randy Kolehouse*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 Standard Kent County Monument

- Nail & K.C. remon. tag on SE side p. pole S 45° W 50.91'
- Nail & K.C. remon. tag on NW side p. pole N 45° E 51.59'
- NW corner house fnd. S 45° E 84.40'
- C/L water valve N 25° W 33.48'



Signed by *Randy J. Kolehouse*  
Surveyor's Michigan License No. 25854

Date 11/21/94