

**SURVEY & REMONUMENTATION**

APR 28 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 94 DEC -6 AM 8:57

For corners in

	<u>Kent</u> (County)	Located in:	Corner Code #
1. Public Land Survey		T <u>6N</u> R <u>12W</u>	<u>B-10</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

*Eric J. Bond*  
 REG. OF DEEDS

**7724**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	V
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	20	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on October 8 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

B-10 This corner was not originally set by the G.L.O.

Year	Survey Records	Surveyor	Monument
1948	Survey Records	Williams & Works	Concrete Mon.
1972	L.C.R.C. #242	Williams & Works	1" Iron
1978	L.C.R.C. #782	Williams & Works	1" Pipe

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 10/12/94  
 CHAIRMAN *Henry Hubert*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

B-10 Found 1" pipe 2' ± East of the C/L of Canal Avenue running N-S. This point checks Williams & Works survey records and L.C.R.C.'s #242 and #782. This point is being used for several subdivisions 1" pipe is 44.0' South and 5.1' West of the intersection of 1/4 lines. Accepted 1" pipe as Center Section.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B-10 Replaced 1" pipe with Standard 4" x 30" Kent County Monument.

- Nail & K.C. remon. tag in Twin 10" Maple N 40° E 43.87'
- Nail & K.C. remon. tag in Twin 16" Ash S 30° W 38.41'
- Top C/L hyd. S 70° W 24.73'
- Nail in tele. pole S 25° E 8.61'



Signed by *Randy J. Kolehouse* Date 12/1/94  
 Surveyor's Michigan License No. 25854