

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in **COMMISSION**

Kent (County)	Located in:	Corner Code #	
1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>B-12</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -6 AM 8:57

Lucy Bond
REG. OF DEEDS

7725

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Randy Kolehouse, in a field survey on April 19 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-12 This corner was not originally set by the G.L.O.

1959	Survey Records	Williams & Works	Set Iron at Intersect. 1/4 Line
1959-1974	Survey Records	Williams & Works	Uses Iron/Set in 1959
1971	L.C.R.C. #57	Williams & Works	Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-12 Found P.K. nail over a "T" iron as set by Williams & Works in 1959. Checks witness L.C.R.C. #57 and also Williams & Works 1959 survey. P.K. is 0.2' South and 0.6' East of intersection of 1/4 lines. Accepted P.K. & "T" iron as Center Section.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/28/94
CHAIRMAN *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-12 Replaced P.K. nail and "T" iron with Standard 4" x 30" Kent County Monument (Harrison).

- P.K. in E side post South 56.99'
- P.K. in NW side 24" Hickory S 30° W 94.48'
- Nail in SW side Twin 20" Oak N 30° W 41.03'
- P.K. in S side p. pole N 55° E 81.78'
- Top C/L hyd. S 25° E 115.46'



Signed by *Randy J. Kolehouse* Date 12/1/94
Surveyor's Michigan License No. 25854