

# SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995 LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
**COMMISSION**

94 NOV 29 AM 9:18

*W. J. Bond*  
REG. OF DEEDS

For corners in  
Kent  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 6N R 12W
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

C-1  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

7405

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on July 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-1	1831	G.L.O. Notes	L. Lyon	Set Post
	1935	Wit. Map	K.C. Surveyor	Iron
	1977	L.C.R.C. #1046	Williams & Works	1/2" Rebar
	1982	L.C.R.C. #3140	Moore & Bruggink	Fnd. Iron/Set K.C. Monument
	1990	L.C.R.C. #5562	Thomas Starr	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED *8/11/94*

CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by Moore & Bruggink, Inc., on 8/12/82 and was recorded per L.C.R.C. #3140

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 Found K.C. Monument on North edge Hall Street pavement per L.C.R.C. #3140 & #5562 as set by Glen Hackbardt in place at a 1/2" rebar over a 3/4" pipe he found using L.C.R.C. #1046.

L.C.R.C. #3140

L.C.R.C. #5562


Harrison monument E 48.84'  
K.C. nail & tag 22" Oak S 52.15'

Harrison monument E 48.84'  
SE cor. of hse. N 40° W 73.37'  
K.C. nail & tag N side 14" dbl. Oak N 70° W 63.84'  
K.C. nail & tag SE side 16" Oak S 50° W 66.99'  
K.C. nail & tag W side 24" Oak S 22° W 51.73'  
K.C. nail & tag E side 22" Oak S 52.15'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Standard Kent County Monument  
Standard K.C. monument E 48.84'  
SE cor. of hse. N 40° W 73.37'  
Nail & K.C. remon. tag N side 14" dbl. Oak N 70° W 63.84'  
Nail & K.C. remon. tag SE side 16" Oak S 50° W 66.99'  
Nail & K.C. remon. tag W side 24" Oak S 22° W 51.73'  
Nail & K.C. remon. tag E side 22" Oak South 52.15'



Signed by *Randy J. Kolehouse*  
Surveyor's Michigan License No. 25854

Date 11/21/94