

# SURVEY & REMONUMENTATION

Kent County Remonumentation

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 NOV 29 AM 9:18

*W. J. Bond*  
REG. OF DEEDS

For corners in  
Kent

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>C-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7407

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on April 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-4	1831	G.L.O. Notes	L. Lyon	Set Post	P.A. 345 1990 KENT COUNTY
	1940	Survey Note	Williams & Works	NA	PEER APPROVED <u>9/22/94</u>
	1960	Survey Note	Williams & Works	NA	CHAIRMAN <u>Harry Huber</u>
	1975	Survey Note	Moore & Bruggink	NA	
	1990	L.C.R.C. #5323	John C. Bueche	Set K.C. Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by John C. Bueche on 3/20/90 and was recorded per L.C..R.C. #5323.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


C-4 Found K.C. Monument per L.C.R.C. #5323 as set by John C. Bueche using survey records from Williams & Works 1940-1960 and Moore & Bruggink 1975.  
L.C.R.C. #5323

Remon. tag & nail in S side 12" Ash N 70° W 5.55'	Remon. tag & nail in W side 18" Ash S 25° W 34.68'
Remon. tag & nail in N side 16" Ash N 85° W 38.65'	Remon. tag & nail in SW side 24" Ash S 50° E 34.72'
Remon. tag & nail in S side 12" Ash N 40° W 54.81'	E. edge river W 86' ±
Remon. tag & nail in E side 10" Ash N 15° E 31.12'	C/L blacktop Indian Mounds Dr. E. 150' ±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4 Standard Kent County Monument  
Nail & K.C. remon. tag in S side 12" Ash N 70° W 5.55'  
Nail & K.C. remon. tag in N side 16" Ash N 85° W 38.65'  
Nail & K.C. remon. tag in S side 12" Ash N 40° W 54.81'  
Nail & K.C. remon. tag in E side 10" Ash N 15° E 31.12'  
Nail & K.C. remon. tag in W side 18" Ash S 25° W 34.68'  
Nail & K.C. remon. tag in SW side 24" Ash S 50° E 34.72'  
E. edge river W 86' ±  
C/L blacktop Indian Mounds Dr. E. 150' ±



Signed by Randy J. Kolehouse  
Surveyor's Michigan License No. 25854

Date 11/21/94