

**SURVEY & REMONUMENTATION**

APR 28 1995

Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 NOV 29 AM 9:18

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Tim J. Bond*  
REG. OF DEEDS

For corners in  
Kent  
(County)

Located In:

Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>6N</u> R <u>12W</u> | <u>C-5</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

7408

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on July 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-5	1831	G.L.O. Notes	L. Lyon	Set Post
	1935	Wit. Map	K.C. Surveyor	Iron
	1973	L.C.R.C. #482	Williams & Works	1" Iron in Mon. Box
	1982	L.C.R.C. 2698	Jonker	1/2" Copper Rod in Mon. Box/Set K.C. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by Jonker Land Surveys on 3/9/82 and was recorded per L.C.R.C. #2698.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5 Found K.C. Monument per L.C.R.C. 2698 as set by Rob Jonker in place of a 1/2" copper rod in Monument Box which he found using L.C.R.C. #482.

L.C.R.C. #2698


NE cor. brick bldg. S 30° W 90.83'  
Face steel guy pole at grade S 82° W 102.96'  
C/L M.H. S 43° E 14.35'  
C/L M.H. N 13° E 50.61'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 8/11/94  
CHAIRMAN *Harry Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5 Standard Kent County Monument  
NE cor. brick bldg. S 30° W 90.93'  
Face steel guy pole at grade S 82° W 102.96'  
C/L M.H. S 43° E 14.35'  
C/L M.H. N 13° E 50.61'  
PK Nail & K.C. remon. tag S side p. pole S 65° E 89.63'



Signed by *Randy J. Kolehouse*  
Surveyor's Michigan License No. 25854

Date 11/21/94