

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

Kent County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 NOV 29 AM 9:18

*Tim J. Bond*  
REG. OF DEEDS

For corners in  
Kent

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>12W</u>	C-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7409  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on March 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6	1831	G.L.O. Notes	L. Lyon	Set Post	
	1939	Survey Notes	Williams & Works	N/A	P.A. 345 1990 KENT COUNTY
	1983	Survey Notes	Jonker	P.K.	PEER APPROVED 1/9/22/94
	N/A	Survey Notes	Exxel Engineering	P.K.	CHAIRMAN <i>Randy Kolehouse</i>
	1984	L.C.R.C. 3828	Exxel Engineering	"+" on M.H. Rim	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by Exxel Engineering on 4/13/84 and was recorded per L.C.R.C. #3828.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6 Reset "+" on MH rim using witnesses L.C.R.C. #3828 which was set by Exxel Engineering using survey records from Williams & Works (1939).

L.C.R.C. #3828

- NE cor. bldg. fndn. (conc.) S 37° W 54.90'
- NW cor. hse. fndn. (conc.) S 44° E 90.95'
- SW cor. hse. fndn. (stone) N 40° E 72.16'
- C/L M.H. N 40° W 26.00'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 "+" cut on MH rim  
NE cor. bldg. fndn. (conc. covered w/siding) S 50° W 54.70'  
NW cor. hse. fndn. (conc.) S 40° E 90.98'  
SW cor. hse. fndn. (stone) N 45° E 72.15'  
C/L M.H. N 40° W 26.04'



Signed by *Randy J. Kolehouse*  
Surveyor's Michigan License No. 25854

Date 11/21/94