

SURVEY & REMONUMENTATION

APR 28 1995

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 94 NOV 29 AM 9:18
Filing Requirement of Act 74, Mich. P.A. 1970

Tim J. Bond
REG. OF DEEDS

For corners in Kent (County)

Located In: Corner Code #/

1. Public Land Survey	T 6N R 12W	C-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

7412
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on March 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-9	1831	G.L.O. Notes	L. Lyon	Set Post
	1974	L.C.R.C. #695	Williams & Works	"T" Iron
	1974	L.C.R.C. #782	Englert	"T" Iron
	1981	L.C.R.C. 1958	Exxel Engineering	Fnd. "T" Iron/Set K.C. Mon.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering, Inc., on 8/31/81 and was recorded per L.C.R.C. #1958.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 Found K.C. Monument in the C/L intersection of Wilson Avenue running N-S and 44th Street running E-W per L.C.R.C. #1958 which was set in place of "T" Iron found by Exxel Eng. which checks L.C.R.C. #695 and #782.

L.C.R.C. #1958

SW cor. hse. fndn. N 38° E 133.26'
Top of C/L hydrant N 79° W 152.03'
At C/L "X" of roads

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/28/94
CHAIRMAN *Harry Hubert*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 Standard Kent County Monument
Nail & K.C. remon. tag in NW side p. pole S 49° W 61.28'
SE cor. catch basin S 32° E 47.08'
SW cor. hse. fndn. N 38° E 133.26'
Top of C/L hydrant N 79° W 152.03'
At C/L "X" of roads



igned by *Randy J. Kolehouse* Date 11/21/94
urveyor's Michigan License No. 25854