

**SURVEY & REMONUMENTATION**

Kent County Remonumentation

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

NOV 29 AM 9:18

*Lee J. Bond*  
REG. OF DEEDS

7413

Register of Deeds Stamp & File Number

For corners in Kent (County)	Located In:	Corner Code #/
1. Public Land Survey	T6N R 12W	C-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on March 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-10	1831	G.L.O. Notes	L. Lyon	Set Post
	1944	Wit. Map	K.C. Surveyor	2" Iron
	1972	L.C.R.C. #364	Exxel Engineering	1" Iron in M.B.
	1974	L.C.R.C. #782	Englert	1 1/2" Iron
	1981	L.C.R.C. #1960	Exxel Engineering	Fnd. 1" Iron in M.B./Set K.C. Mon.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering, Inc., on 8/7/81 and was recorded per L.C.R.C. #1960.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10 Found K.C. Monument in monument box in the approximate C/L of Wilson Avenue running N-S which was set by Exxel Engineering in place of a 1" iron pipe in monument box, which checked using L.C.R.C.'s #364 and #782.

L.C.R.C. #1960

Nail & K.C. remon. tag in East side 24" Box Elder S 10° E 177.62'  
SE cor. hse. fndn. N 65° W 85.88'  
NE cor. gar. fndn. N 40° W 121.04'  
C/L hydrant N 10° E 177.05'  
C/L road East 3.0'

P.A. 345 1980 KENT COUNTY  
PEER APPROVED 7/28/94  
CHAIRMAN Harry Huber

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-10 Standard Kent County Monument  
Nail & K.C. remon. tag in East side 24" Ash S 10° E 177.62'  
SE cor. hse. fndn. N 65° W 85.88'  
NE cor. gar. fndn. N 40° W 121.04'  
C/L hydrant N 10° E 177.05'  
C/L road East 3.0'  
PK nail & K.C. remon. tag N face p. pole West 21.77'



Signed by Randy J. Kolehouse Date 11/21/94  
Surveyor's Michigan License No. 25854