

# SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE 94 NOV 29 AM 9:18  
Filing Requirement of Act 74, Mich. P.A. 1970

## COMMISSION

For corners in  
Kent

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>D-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. J. Bond*  
REG. OF DEEDS

7417

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on August 31, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1	This corner was not originally set by the G.L.O.			
1913-1964	Survey Notes	Williams & Works	Iron	
1985	L.C.R.C. #4120	William Byl	Fnd. Iron/Set K.C. Mon.	
1990	L.C.R.C. #5563	Thomas Starr	K.C. Monument	

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 8/22/94  
CHAIRMAN *Henry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by William R. Byl on 1/3/85 and was recorded per L.C.R.C. #4120.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


D-1 Found K.C. Monument per L.C.R.C.'s #4120 and #5563 as set by William Byl in place of a 1" iron he found and checked using Williams & Works survey records from 1913 to 1964.

L.C.R.C. #4120	L.C.R.C. #5563
Nail & tag W side 18" Oak S 45° E 3.59'	Nail & K.C. remon. tag W side 18" Oak S 45° E 3.59'
Nail & tag S side 18" Hickory N 85° E 41.56'	Nail & K.C. remon. tag S side 18" Hickory N 85° E 41.56'
Nail & tag N side 18" Beech S 80° E 20.21'	Nail & K.C. remon. tag N side 18" Beech S 80° E 20.21'
Nail & tag W side 12" Oak N 00° E 36.63'	Nail & K.C. remon. tag W side 12" Oak N 00° E 36.63'
Nail & tag N side 18" Hickory S 90° W 32.97'	Nail & K.C. remon. tag N side 18" Hickory S 90° W 32.97'
	On tree ROW E & W K.C. mon. W 274.34'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Standard Kent County Monument  
Nail & K.C. remon. tag W side 18" Oak S 45° E 3.58'  
Nail & K.C. remon. tag S side 18" Hickory N 85° E 41.56'  
Nail & K.C. remon. tag N side 18" Beech S 80° E 20.21'  
Nail & K.C. remon. tag W side 12" Oak N 00° E 36.63'  
Nail & K.C. remon. tag N side 18" Hickory S 90° W 32.97'  
On tree ROW E & W  
Kent County Monument West 274.34



igned by Randy J. Kolehouse  
urveyor's Michigan License No. 25854

Date 11/21/94