

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

94 DEC -6 AM 8:57

Lucy Bond
 REG. OF DEEDS

For corners in

<u>Kent</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>D-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7727

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on April 25 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-4 This corner was not originally set by the G.L.O.

1928	Survey Records	Williams & Works	Set Iron
1928-1967	Survey Records	Williams & Works	Used Same Iron
1963	Wit. Map (MDOT)	K.C. Surveyor	Iron Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-4 Found capped iron #15406 (Williams & Works) at the location of iron set by Williams & Works in 1928. This point was originally set on the N-S 1/4 line at the intersection with the North line of Manwaring Park 327.8' East of the NW corner of said plat. This iron is 1.0' North and 1.0' West of the intersection of 1/4 lines. Accepted iron as Center Section.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/22/94

CHAIRMAN Harry Huber

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-4 Replaced capped iron with a Standard 4" x 30" K.C. Monument.

- Nail in E side p. pole North 15.85'
- SW cor. metal bldg. N 72° E 70.28'
- SE cor. concrete hoist pad N 28° W 37.55'
- Exxel iron East 66.03'



igned by Randy J. Kolehouse
 urveyor's Michigan License No. 25854

Date 12/1/94