

SURVEY & REMONUMENTATION

APR 28 1995

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -6 AM 8:57

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>12W</u>	D-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Luigi J. Jond
REG. OF DEEDS

7731

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on October 10 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-10 This corner was not originally set by the G.L.O.

1907-1961	Survey Records	Williams & Works	Fence Cor. Used Intersect 1/4 Lines
1961	Survey Records	Williams & Works	Fence Cor. Used Intersect 1/4 Lines
1972	L.C.R.C. #364	Exel Engineering	Set Iron at Intersection 1/4 Line

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-10 Found Kent County Monument which checks L.C.R.C. #364 and Williams & Works survey records (1961). Monument is 0.3' North and 0.2' East of intersection of 1/4 lines. Accepted Kent County Monument as Center Section.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/28/94
CHAIRMAN *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-10 Kent County Monument
- Nail in E side 16" Ash S 20° W 40.92'
 - Nail in E side 36" Ash South 155.90'
 - Nail in N side wood fence post S 70° E 36.84'
 - Nail & tag in N side 12" Ash S 85° W 10.23'



Signed by *Randy J. Kolehouse* Date 12/1/94
Surveyor's Michigan License No. 25854