

SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 29 AM 9:18

COMMISSION

Tim J. Bond
REG. OF DEEDS

7421

Register of Deeds Stamp & File Number

For corners in Kent (County) Located In: _____ Corner Code D-11

1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on March 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-11	1831	G.L.O. Notes	L. Lyon	Set Post
	1953	Wit. Map	K.C. Surveyor	1-1/2" Iron
	1973	L.C.R.C. #439	Medema Van Kooten	Iron
	1981	L.C.R.C. #1963	Exxel Engineering	Fnd. "T" Iron/Set K.C. Mon.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering, Inc., on 8/31/81 and was recorded per L.C.R.C. #1963.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 Found K.C. Monument in C/L of 52nd Street running E-W as set by Exxel Engineering. Checks the following witnesses.
L.C.R.C. #1963

SE cor. concrete block barn N 52° W 197.98'
Nail & K.C. remon. tag in S side light pole N 86° E 158.61'
C/L road 1.2' South

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/28/94
CHAIRMAN *[Signature]*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11 Standard Kent County Monument
Found "+" end of 36" conc. culv. N 50° E 36.73'
Found "+" end of 15" conc. culv. S 05° E 24.33'
Nail & K.C. remon. tag in S side light pole N 86° E 159.22'
C/L top of hyd. N 74° W 88.85'



Signed by *Randy J. Kolehouse* Date 11/21/94
Surveyor's Michigan License No. 25854