

SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 29 AM 9:18

Luigi J. Bond
REG. OF DEEDS

For corners in **COMMISSION**
Kent
(County)

Located In: Corner Code ##

1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>D-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

7422

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on June 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13	1831	G.L.O. Notes	L. Lyon	Set Post
	N/A	Survey Records	Williams & Works	Iron at Fence Corner
	1976	Survey Records	Exxel Engineering	1/2" Iron
	1981	L.C.R.C. #1967	Exxel Engineering	Fnd. 1/2" Iron/Set K.C. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by Exxel Engineering on 7/8/81 and was recorded per L.C.R.C. #1967.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found K.C. Monument at remains of fence corner per L.C.R.C. #1967 as set by Exxel Engineering in place of a 1/2" iron that they found which checks Williams & Works and Exxel Engineering survey records.

L.C.R.C. #1967

Nail & K.C. tag in W side 20" Maple S 9° W 19.78'
Nail & K.C. tag in N side 10" Cherry S 60° W 34.62'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/22/94
CHAIRMAN *Randy Kolehouse*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Standard Kent County Monument
Nail & K.C. remon. tag in W side 20" Maple S 9° W 19.78'
Nail & K.C. remon. tag in N side 10" Cherry S 60° W 34.62'
Nail & K.C. remon. tag in NW side 30" Maple N 83° E 73.81'



Signed by *Randy J. Kolehouse* Date 11/21/94
Surveyor's Michigan License No. 25854