

SURVEY & REMONUMENTATION

Kent County Remonumentation

APR 28 1995

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 29 AM 9:19

For corners in
Kent

Located In:

Corner Code #

(County)

- 1. Public Land Survey T 6N R 12W
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

E-12

Lucy Bond
REG. OF DEEDS

7434

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse in a field survey on March 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12	1831	G.L.O. Notes	L. Lyon	Set Post
	N/A	Wit. Map	K.C. Surveyor	Iron
	1972	L.C.R.C. #241	Williams & Works	1/2" Iron
	1981	L.C.R.C. #1834	Exxel Engineering	Fnd. 1/2" Iron/Set K.C. Mon.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/28/94
CHAIRMAN *Randy Kolehouse*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering, Inc., on 6/2/81 and was recorded per L.C.R.C. #1834.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12 Found K.C. Monument in C/L of Ivanrest Avenue running N-S on C/L of 56th Street running E-W per L.C.R.C. #1834 as set by Exxel Engineering in place of 1/2" iron found and checked to K.C. Surveyor's wit. map and L.C.R.C. #241.

L.C.R.C. #1834

Nail & K.C. remon. tag in SW side 26° Aspen N 60° W 92.66'
C/L top of hydrant S 75° E 144.47'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-12 Standard Kent County Monument
- Nail & K.C. remon. tag in SE face p. pole N 45° E 39.16'
- Nail & K.C. remon. tag in SE face p. pole S 45° W 46.57'
- Nail & K.C. remon. tag in SW face p. pole N 50° W 52.09'
- Nail & K.C. remon. tag in SW face 26° Aspen N 60° W 92.66'
- C/L top of hydrant S 75° E 144.47'



Signed by *Randy J. Kolehouse* Date 11/21/94
Surveyor's Michigan License No. 25854