

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

94 DEC -6 AM 8:57

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>F-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

W. J. Bond
 REG. OF DEEDS

7734

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on August 8 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11	12
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-4 This corner was not originally set by the G.L.O.

1932-1961	Survey Records	Williams & Works	"+" in Pavement
1976	Survey Records	Williams & Works	Bt. Spike
1976	L.C.R.C. #927	Williams & Works	Bt. Spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-4 Found bt. spike per witness L.C.R.C. #927 per Williams & Works survey records. This point checks the same location as the "+" in pavement used from 1932-1961. The bt. spike is 3.6' South and 5.9' West of the intersection of 1/4 lines. Held bt. spike as Center Section.

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 12/29/94
 CHAIRMAN Darryl Fisher

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-4 Replaced bt. spike with Standard 4" x 30" Kent County Monument (Harrison).

- SW corner brick hse. N 10° E 83.90'
- SE corner brick hse. N 45° E 122.80'
- Spike and MSHD tag in NW side 26" Walnut S 65° W 63.82'
- Spike and MSHD tag in NE side 24" Maple S 60° E 56.02'



Signed by Randy J. Kolehouse
 Surveyor's Michigan License No. 25854

Date 12/1/94