

SURVEY & REMONUMENTATION

APR 28 1995

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

94 DEC -6 AM 8:58

COMMISSION

For corners in

For corners in	Kent (County)	Located in:	Corner Code #
1. Public Land Survey		T <u>6N</u> R <u>12W</u>	<u>F-6</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

Tim J. Bond
REG. OF DEEDS

7737

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25							
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

I, Randy Kolehouse, in a field survey on May 31 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-6	This corner was not originally set by the G.L.O.		
1928	Survey Records	Williams & Works	Set Iron from Previous Surveys
1928-1961	Survey Records	Williams & Works	Used Iron
1961	Survey Records	Williams & Works	Fnd. Bt. Spike
1972	L.C.R.C. #365	Exxel Engineering	Fnd. Bt. Spike
1976	L.C.R.C. #913	Green	Fnd. Bt. Spike
1984	L.C.R.C. #4047	William Byl	Fnd. Bt. Spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-6 Found P.K. nail in C/L of Prarie Street E-W per L.C.R.C. #4047. This point checks survey measurements (1941-1961) from Williams & Works survey records to the N 1/4, S 1/4, E 1/4 and W 1/4 corners of section ± 0.10' to 0.8'. The P.K. is 1.3' South and 0.2' West of the intersection of 1/4 lines. Accepted P.K. as Center Section.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/29/94
CHAIRMAN *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-6 Replaced P.K. nail with a Standard 4" x 30" Kent County Monument (Harrison).

Nail & K.C. remon. tag in S side p. pole N 70° E 92.27'
Nail & K.C. remon. tag in SW side p. pole N 60° W 64.53'
Top C/L hyd. S 45° W 70.73'
1/2" iron S 45° E 64.90'



Signed by *Randy J. Kolehouse* Date 12/1/94
Surveyor's Michigan License No. 25854