

SURVEY & REMONUMENTATION

Kent County Remonumentation

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 NOV 29 AM 9:19

COMMISSION

For corners in
Kent

(County)

Located In:

Corner Code =#

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>6N</u> R <u>12W</u> | <u>F-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Tim J. Bond
REG. OF DEEDS

7439

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on March 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-7	1831	G.L.O. Notes	L. Lyon	Set Post
	1939	Wit. Map	K.C. Surveyor	Stone
	1974	L.C.R.C. #686	Exxel Engineering	1" Iron
	1976	L.C.R.C. #912	Greer	Iron Pipe
	1982	L.C.R.C. #2697	Jonker	1" Iron & Stone/Set K.C. Mon.
	1984	L.C.R.C. #4048	William Byl	Reset K.C. Mon.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/28/94

CHAIRMAN *Harry Thibodeau*

This corner was originally approved by the Kent County Remonumentation Peer Group monumented by Jonker Land Surveys on 3/9/82 and was recorded per L.C.R.C. #2697.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 Found K.C. Monument at SW edge bit. (36th Street E) per L.C.R.C.'s #2697 and #4048 as set by Jonker in place of a 1" iron pipe over a 10"x10"x22" pointed stone which he found and checked with L.C.R.C.'s #686 and #912.

L.C.R.C. #2697

L.C.R.C. #4048

K.C. remon. tag on SE side p. pole N 51° E 48.15'
K.C. remon. tag on S side g. pole S 85° W 32.73'

K.C. remon. tag on SE side p. pole N 51° E 48.15'
K.C. remon. tag on S side g. pole S 85° W 32.73'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-7 Standard Kent County Monument
Nail & K.C. remon. tag on SE side p. pole N 51° E 48.15'
Nail & K.C. remon. tag on S side g. pole S 85° W 32.73'
NE cor. house foundation (#3595) N 45° W 97.10'
SE cor. house foundation (#3580) N 60° E 199.55'
SW cor. house foundation (#2776) S 55° E 175.27'
C/L M.H. N 05° W 9.20'



Signed by *Randy J. Kolehouse*
Surveyor's Michigan License No. 25854

Date 11/21/94