

SURVEY & REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

94 DEC -6 AM 8:58

For corners in
Kent **COMMISSION**
(County)

Located in:	Corner Code #
T <u>6N</u> R <u>12W</u>	<u>F-10</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

W. J. Bond
REG. OF DEEDS

7735

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. _____, Recorded Plat _____
- Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on October 6 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-10 This corner was not originally set by the G.L.O.

1959	Survey Records	Williams & Works	Set Iron at Intersect. 1/4 Lines
1959-1971	Survey Records	Williams & Works	Iron
1971	L.C.R.C. #53	Williams & Works	Solid Iron
1987	L.C.R.C. #4938	Exel Engineering	Fnd. Solid Iron/Set K.C. Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-10 Found aa K.C. Monument per L.C.R.C. #4938. Checks Williams & Works survey records of 1959 ± 0.2' to N 1/4, W 1/4 and S 1/4 corners of section and ± 0.8' to E 1/4 corner. Also checks L.C.R.C. #53. This iron in 0.70' North of the intersection of 1/4 lines. Accepted K.C. Mon. as Center Section.

P.A. 3-13 1970 KENT COUNTY
PEER APPROVED 7/28/94
CHAIRMAN *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-10 Replaced iron with a Standard 4" x 30" Kent County Monument (Harrison).

Nail & K.C. remon. tag in SW side 6" Maple N 45° W 5.67'
Nail & K.C. remon. tag in SW side 10" Oak N 20° W 13.17'
Nail & K.C. remon. tag in SE side 6" Maple S 30° W 13.22'
Nail & K.C. remon. tag in N side p. pole S 80° W 77.31'
C/L 2" steel fence post S 40° E 1.46'



Signed by Randy J. Kolehouse Date 12/1/94
Surveyor's Michigan License No. 25854