

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

DEC -6 AM 8:58

For corners in
Kent **COMMISSION**
(County)

Located in:	Corner Code #
T <u>6N</u> R <u>12W</u>	<u>F-12</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

Peer Approved
REG. OF DEEDS

7736

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on April 19 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-12 This corner was not originally set by the G.L.O.

1956	Survey Records	Williams & Works	Iron
1956-1972	Survey Records	Williams & Works	Iron
1973	L.C.R.C. #507	Williams & Works	Reset "T" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-12 Found P.K. nail in C/L 56th Street per L.C.R.C. #507. This point is 2.7' South and 1.0' East of the intersection of 1/4 lines which checks Williams & Works survey records from 1956. Accepted P.K. nail as Center Section.

P.A. 345 1990 KENT COUNTY,
PEER APPROVED 7/28/94
CHAIRMAN *Harry Huber*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-12 Replaced P.K. nail with a Standard 4" x 30" Kent County Monument (Harrison).

- Nail in E side 6" Oak N 05° W 38.16'
- Nail in NW side p. pole N 60° E 132.45'
- Nail in W side 6" Oak South 46.27'
- Nail in NE side p. pole N 50° W 67.24'



Signed by Randy J. Kolehouse Date 12/1/94
Surveyor's Michigan License No. 25854