

SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE NOV 29 AM 9:19
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kent **COMMISSION**
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>6N</u> R <u>12W</u> | <u>F-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

W. J. Dand
REG. OF DEEDS

7442

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on March 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13	1831	G.L.O. Notes	L. Lyon	Set Post
	N/A	Survey Records	Williams & Works	1" Iron
	1973	L.C.R.C. #507	Williams & Works	1" Iron
	1981	L.C.R.C. #1793	Williams & Works	Fnd. 1" Iron/Set K.C. Mon.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works, Inc., on 5/19/91 and was recorded per L.C.R.C. #1793.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Found K.C. Monument per L.C.R.C. #1793 as set by Williams & Works in place of a 1" Iron they found and checked to survey records and L.C.R.C. #507.

L.C.R.C. #1793

- K.C. remon. tag & nail in N side 8" W Cherry S 70° E 36.65'
- K.C. remon tag & nail in W side 2" Maple N 45° E 2.87'
- K.C. remon tag & nail in W side 4" Sass. N 35° W 10.79'
- K.C. remon tag & nail in E side 4" Oak S 10° W 9.87'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/28/94
CHAIRMAN Harry Huber

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-13 Standard Kent County Monument
- K.C. remon. tag & nail in N side 8" W Cherry S 70° E 36.65'
 - K.C. remon tag & nail in W side 2" Maple N 45° E 2.87'
 - K.C. remon tag & nail in W side 4" Sass. N 35° W 10.79'
 - K.C. remon tag & nail in E side 4" Oak S 10° W 9.87'



Signed by Randy J. Kolehouse
Surveyor's Michigan License No. 25854

Date 11/21/94