

SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 29 AM 9:19

For corners in Kent **COMMISSION**
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 6N R 12W
- 2. Property Controlling in Section S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____

G-2

Lee J. Bond
REG. OF DEEDS

7444

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on April 22, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-2	1831	G.L.O. Notes	L. Lyon	Set Post
	1895	Survey Records	Williams & Works	Iron at Fence Corner
	1956	Survey Records	Williams & Works	Iron at Fence Corner
	1963	Wit. Map	K.C. Surveyor (MDSH)	1" Iron Pipe
	1985	L.C.R.C. #4266	William Byl	Fnd. 1" Iron/Set K.C. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by William R. Byl on 7/29/85 and was recorded per L.C.R.C. #4266.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2 Found K.C. Monument per L.C.R.C. #4266 as set by William Byl in place of a 1" Iron over a 1-1/4 iron which he found and checked with Williams & Works survey records 1895 and 1956.

L.C.R.C. #4266

- Nail & tag in N side 10" Ash N 90° E 17.34'
- Nail & tag in E side 12" Twin Maple N 30° E 30.61'
- Nail & tag in E side 52" Oak N 00° E 100.95'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/22/94
CHAIRMAN Harry Hubert

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-2 Standard Kent County Monument
- Nail & K.C. remon. tag in N side 10" Ash N 90° E 17.34'
- Nail & K.C. remon. tag in E side 12" Twin Maple N 30° E 30.61'
- Nail & K.C. remon. tag in E side 52" Oak N 00° E 100.95'
- Nail & K.C. remon. tag in NW side 4" Ash S 80° W 26.92'
- Nail & K.C. remon. tag in E side 4" Ash S 35° W 22.45'



Signed by Randy J. Kolehouse
Surveyor's Michigan License No. 25854

Date 11/21/94