

SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 29 AM 9:19

For corners in **COMMISSION**
Kent
(County)

Located In:	Corner Code #
1. Public Land Survey T 6N R 12W	G-5
T R	
T R	
T R	
2. Property Controlling S T R	
in Section S T R	
3. Miscellaneous S T R	
Property in Sec. S T R	

W. J. Sand
REG. OF DEEDS

7447

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on April 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-5	1831	G.L.O. Notes	L. Lyon	Set Post
	1956	Wit. Map	K.C. Surveyor	Mon. Box
	1971	L.C.R.C. #52	Williams & Works	1" Iron In Mon. Box
	1982	L.C.R.C. #3036	Jonker	Fnd. 1" Iron in Mon. Box/Set K.C. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by Jonker Land Surveys on 7/21/82 and was recorded per L.C.R.C. #3036.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 Found P.K. nail per L.C.R.C. #3036. Monument as set by Rob Jonker over the top of a 1" iron in monument box, which checked wit. map and L.C.R.C. #52 has been destroyed, P.K. nail checks L.C.R.C. #3034.

L.C.R.C. #3036

SW cor. brick bldg. N 50° E 111.0'
SE cor. church fndn. N 50° W 86.90'
Remon. tag on W side p. pole S 30° E 74.45'
C/L M.H. S 20° W 61.95'

P.A. 345 1990 KENT COUNTY


PEER APPROVED *8/11/94*

CHAIRMAN *Hamp Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 Set Standard Kent County Monument
SW cor. brick bldg. N 50° E 111.0'
SE cor. church fndn. N 50° W 86.90'
Nail & K.C. remon. tag on W side p. pole S 30° E 74.38'
C/L M.H. S 20° W 61.95'



Signed by *Randy J. Kolehouse*
Surveyor's Michigan License No. 25854

Date 11/21/94