

**SURVEY & REMONUMENTATION**

Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 29 AM 9:19

For corners in Kent **COMMISSION**  
(County)

Located In: Corner Code #

*Tim Bond*  
REG. OF DEEDS

- 1. Public Land Survey T 6N R 12W G-6
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

7448

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on April 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-6	1831	G.L.O. Notes	L. Lyon	Set Post
	1956	Wit. Map	K.C. Surveyor	Iron in Concrete
	1971	L.C.R.C. #52	Williams & Works	Iron in Concrete
	1975	L.C.R.C. #799	Moore & Bruggink	Iron in Concrete
	1976	L.C.R.C. #913	Greer	3/4" Iron
	1982	L.C.R.C. #3037	Jonker	Fnd. 1/2" Iron/Set K.C. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by Jonker Land Surveys on 7/20/82 and was recorded per L.C.R.C. #3037.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 Found K.C. Monument in C/L Byron Center Avenue running N-S 12' M/L South of C/L Praire Street running E-W per L.C.R.C. #3037 as set by Rob Jonker in place of a 1/2" iron he found which checked L.C.R.C.'s #52, #799 and #913.  
L.C.R.C. #3037


- Remon. tag W side t. pole N 40° E 66.25'
- Remon. tag E side p. pole N 35° W 58.02'
- Remon. tag curb joint S 65° E 33.85'
- NE cor. hse. brick S 60° W 97.05'
- C/L M.H. N 40° W 27.96'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 8/11/94  
CHAIRMAN *[Signature]*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-6 Standard Kent County Monument
- Nail & K.C. remon. tag W side t. pole N 40° E 66.25'
- Nail & K.C. remon. tag E side p. pole N 35° W 58.02'
- Nail & K.C. remon. tag curb joint S 65° E 33.85'
- NE cor. hse. brjck S 60° W 97.05'
- C/L M.H. N 40° W 27.96'



Signed by *Randy J. Kolehouse*  
Surveyor's Michigan License No. 25854

Date 11/21/94