

SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 29 AM 9:22

For corners in Kent **COMMISSION**
(County)

Located In: Corner Code #

- 1. Public Land Survey T 6N R 12W H-7
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
In Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property In Sec. S _____ T _____ R _____

Wit Bond
REG. OF DEEDS

7459

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on April 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7	1831	G.L.O. Notes	L. Lyon	Set Post
	1939	Wit Map	KC Surveyor	Iron s/BT SPK
	1957	Wit Map	KC Surveyor	Iron s/BT/SPK
	1975	L.C.R.C. #858	Modema Van Kooten	Solid Iron
	1982	L.C.R.C. #2695	Jonker	Fnd solid iron
	1988	L.C.R.C. #4681	J. Bueche	Set KC Mon.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/28/94
CHAIRMAN [Signature]

This corner was originally approved by the Kent County Remonumentation Peer Group monumented by Jonker Land Surveys on 3/19/82 and was recorded per L.C.R.C. #2695 and also recorded 7/26/88 per L.C.R.C. #4681.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Found KC Monument in centerline 36th St. running E-W per L.C.R.C. #2695 and #4681 as set by Rob Jonker in place of a solid iron he found and checked with 1957 KC Wit Map and L.C.R.C. #858.

L.C.R.C. #2695

L.C.R.C. #4681


K.C. remon. tag on E side t. pole S 0° W 32.82'
SW corner hse. fnd. N 15° E 70.24'
SW corner bottom conc. step N 25° W 72.75'
NW corner hse. fnd. S 45° W 72.72'
S. face vertical ret. wall N 0° E 46.62'

K.C. remon. tag on E side t. pole S 0° W 32.82'
SW corner hse. fnd. N 15° E 70.24'
SW corner bottom conc. step N 25° W 72.75'
NW corner hse. fnd. S 45° W 72.72'
S. face vertical ret. wall N 0° E 46.62'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 Standard Kent County Monument
K.C. remon. tag on E side t. pole S 0° W 32.82'
SW corner hse. fnd. N 15° E 70.24'
SW corner bottom conc. step N 25° W 72.75'
NW corner hse. fnd. S 45° W 72.72'
S. face vertical ret. wall N 0° E 46.62'



Signed by Randy J. Kolehouse
Surveyor's Michigan License No. 25854

Date 11/21/94