

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC -6 AM 8:58

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>H-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Terry J. Bond*  
REG. OF DEEDS

7743

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on June 14 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-10	This corner was not originally set by the G.L.O.
1928	Survey Records Williams & Works Set Iron
1973	L.C.R.C. #594 Exxel Engineering 3/4" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-10 Set point per Plat of Chateau Estates No. 4 for Center Section. This point checks location of Center Section set by Williams & Works in 1928 and L.C.R.C. #594. Point is 0.7' South and 0.9' East of intersection of 1/4 lines.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 7/28/99  
CHAIRMAN *Harry Decker*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-10 Set Standard 4" x 30" Kent County Monument at point established above in "B."

- SW corner house fndn. N 40° E 37.43'
- Nail & K.C. remon. tag in E side 34" Beach N 15° W 42.72'
- Nail & K.C. remon. tag in N side 34" Beach S 70° W 14.16'
- Nail & K.C. remon. tag in SW side 36" Cherry S 45° E 34.05'



Signed by *Randy J. Kolehouse* Date 12/1/94  
Surveyor's Michigan License No. 25854