

SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

94 NOV 29 AM 9:23

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kent

(County)

Located In:

Corner Code =#

1. Public Land Survey	T	6N	R	12W	I-6
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Tim Bond
REG. OF DEEDS

7468

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on April 21, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6	1831	G.L.O. Notes	L. Lyon	Set Post
	1966	Wit. Map	K.C. Surveyor	Solid Iron & Bt. Spike
	1982	L.C.R.C. #3226	Exxel Eng.	Solid Iron
	1983	L.C.R.C. #3291	Glaza Assoc.	Bt. Spike
	1990	L.C.R.C. #5328	John Bueche	Fnd. 1/2" Solid Iron/Set K.C. Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/22/94
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by John C. Bueche on 3/20/90 and was recorded per L.C.R.C. #5328.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Found K.C. Monument at C/L intersection of Burlingame Avenue running N-S and 32nd Street running W per L.C.R.C. #5328 as set by John Bueche in place of a 1/2" solid iron he found which checked K.C. Surveyor's records and L.C.R.C.'s #3226 and #3291.

L.C.R.C. #5328

- NW cor. porch S 73° E 77.41'
- NE cor. porch fnd. S 50° W 129.44'
- SE cor. hse. N 55° W 111.23'
- Back walk E 38.91'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-6 Standard Kent County Monument
 - NW cor. porch S 70° E 77.50'
 - NE cor. porch fnd. S 50° W 129.46'
 - SE cor. hse. N 50° W 111.15'
 - Back walk E 38.91'



Signed by Randy J. Kolehouse
Surveyor's Michigan License No. 25854

Date 11/21/94