

SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE 94 NOV 29 AM 9:23
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kent **COMMISSION**
(County)

Located In: Corner Code #

Lucy J. Bond
REG. OF DEEDS

- 1. Public Land Survey T 6N R 12W I-12
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

7473

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on March 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-12	1831	G.L.O. Notes	L. Lyon	Set Post
	1948	Survey Records	Williams & Works	Iron
	1949	Wit. Map	K.C. Surveyor	Iron
	1972	L.C.R.C. #278	Medema Van Kooten	Square Spike
	1981	I#1831	Exxel Engineering	Fnd. Square Spike/Set K.C. Mon.
	1988	L.C.R.C. #4693	John Bueche	K.C. Mon.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/20/94
CHAIRMAN *Harry Huber*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering, Inc., on 6/2/81 and was recorded per L.C.R.C. #1831.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 Found K.C. Monument at Burlingame Avenue and 56th Street per L.C.R.C.'s #1831 and #4693 as set by Exxel Engineering in place of a square spike which they found and which checks L.C.R.C. #278 of Williams & Works survey records of 1948.


L.C.R.C. #1831
"X" cut mark S side M.H. rim N 76° W 42.16'
Nail in bottle cap in W side t. pole N 20° E 85.14'
Top of hydrant N 73° E 75.20'

L.C.R.C. #4693
"X" cut in top of curb N 68° E 39.70'
"X" cut mark S side M.H. rim N 76° W 42.16'
Nail in bottle cap in W side t. pole N 20° E 85.14'
Top of hydrant N 73° E 75.20'
"X" cut in top curb S 44° E 41.26'
On C/L of roads to N, S, & E, on C/L brush row W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Standard Kent County Monument
Nail & bottle cap in S side p. pole N 80° W 33.38'
"X" cut in top of curb N 68° E 39.70'
"X" cut mark S side M.H. rim N 76° W 42.16'
Nail in bottle cap in W side t. pole N 20° E 85.14'
Top of hydrant N 73° E 75.20'
"X" cut in top curb S 44° E 41.26'
On C/L of roads to N, S, & E, on C/L brush row W



igned by Randy J. Kolehouse
urveyor's Michigan License No. 25854

Date 11/21/94