

**SURVEY & REMONUMENTATION** Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 29 AM 9:23

For corners in Kent

COMMISSION

*W. J. Bond*  
REG. OF DEEDS

For corners in Kent	Located In:	Corner Code =#
(County)		
1. Public Land Survey	T 6N R 12W	K-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7488

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on April 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-7	1831	G.L.O. Notes	L. Lyon	Set Post
	1932	Wit. Map	K.C. Surveyor	Iron in Conc.
	1957	Wit. Map	K.C. Surveyor	Iron in Conc.
	1971	L.C.R.C. #56	Williams & Works	"T" Iron
	1982	L.C.R.C. #2821	Jonker	Fnd. "T" Iron/Set K.C. Mon.
	1988	L.C.R.C. #4703	Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/28/94  
CHAIRMAN Harry Huber

This corner was originally approved by the Kent County Remonumentation Peer Group, monumented by Jonker Land Surveys on 3/30/82 and was recorded per L.C.R.C. #2821.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 Found K.C. Monument at C/L Intersection of 36th Street and Clyde Park per L.C.R.C.'s #2821 and #4703 as set by Rob Jonker in place of a "T" iron he found which was set by Williams & Works in 1971 using survey records of K.C. Surveyor.

L.C.R.C. #2821	L.C.R.C. #4703
C/L M.H. S 25° W 37.71'	C/L M.H. S 25° W 37.71'
C/L M.H. S 10° E 14.28'	C/L M.H. S 10° E 14.28'
C/L M.H. N 60° W 33.00'	C/L M.H. N 60° W 33.00'
C/L M.H. N 25° W 40.10'	C/L M.H. N 25° W 40.10'
C/L M.H. S 08° W 6.60'	C/L M.H. S 08° W 6.60'
On C/L "X" pvt.	On C/L "X" pvt.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7 Standard Kent County Monument  
C/L M.H. S 25° W 37.71'  
C/L M.H. S 10° E 14.28'  
C/L M.H. N 60° W 33.00'  
C/L M.H. N 25° W 40.10'  
C/L M.H. S 08° W 6.60'  
On C/L "X" Pvt.



Signed by Randy J. Kolehouse Date 11/21/94  
Surveyor's Michigan License No. 25854