

# SURVEY & REMONUMENTATION

APR 28 1995

Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

## COMMISSION LAND CORNER RECORDATION CERTIFICATE

94 NOV 29 AM 9:23

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Kent

(County)

Located In:

Corner Code #:

1. Public Land Survey	T 6N R 12W	K-8	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous	S _____ T _____ R _____	_____	_____
Property in Sec.	S _____ T _____ R _____	_____	_____

*Tim J. Bond*  
REG. OF DEEDS

7489

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Randy Kolehouse, in a field survey on April 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

K-8	1831 G.L.O. Notes	L. Lyon	Set Post
	1951 Wit. Map	K.C. Surveyor	Iron in Conc.
	1957 Wit. Map	K.C. Surveyor	Iron in Conc.
	1974 L.C.R.C. #652	Spicer	1" Sq. Iron
	1982 L.C.R.C. #3041	Jonker	Set K.C. Monument
	1988 L.C.R.C. #4704	Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 7/28/94  
CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group monumented by Jonker Land Surveys on 7/20/82 and was recorded per L.C.R.C. #3041.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-8 Found standard Kent County Monument (Harrison) in the center line of Clyde Park Avenue (running North and South) per witness from above L.C.R.C.'s as set by Rob Jonker in place of a 1" x 12" sq. iron which he found using witness ties per County Surveyor's office and Kent County Road Commission records.

L.C.R.C. #3041

L.C.R.C. #4704

K.C. remon. tag on SW side g. pole S 50° E 56.59'  
K.C. remon. tag on NW side p. pole S 55° W 53.35'  
K.C. remon. tag on NW side 9" Pipe N 60° E 66.41'  
C/L M.H. N 45° W 1.85'  
C/L M.H. S 40° E 8.65'

K.C. remon. tag on SW side g. pole S 50° E 56.59'  
K.C. remon. tag on NW side p. pole S 55° W 53.35'  
K.C. remon. tag on NW side 9" Pipe N 60° E 66.41'  
C/L M.H. N 45° W 1.85'  
C/L M.H. S 40° E 8.65'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-8 Standard Kent County Monument  
K.C. remon. tag on SW side g. pole S 50° E 56.59'  
K.C. remon. tag on NW side p. pole S 55° W 53.35'  
K.C. remon. tag on NW side 9" Pipe N 60° E 66.41'  
C/L M.H. N 45° W 1.85'  
C/L M.H. S 40° E 8.65'



Signed by Randy J. Kolehouse Date 11/21/94  
Surveyor's Michigan License No. 25854