

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 29 AM 9:24

For corners in
Kent

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>6N</u> R <u>12W</u> | <u>L-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Lucy J. J. J.
REG. OF DEEDS

7494

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on April 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1 This corner was not originally set by the G.L.O.

1912-1957	Survey Records	Williams & Works	City Iron
1984	L.C.R.C. #4127	William R. Byl	Fnd. 1" Iron/Set K.C. Mon.

The position of this corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 11/28/84 and was recorded per L.C.R.C. #4127.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 Found K.C. Monument per L.C.R.C. #4127 in imbankment of Highway U.S. 131 as set by William Byl in place of a 1" x 36" iron he found which checked Gov. Dist. East of S 1/4 corner, Section 36, T7N R12W, and City survey records.

L.C.R.C. #4127

N face 8" steel light pole S 10° W 22.58'
E face 12" steel guy pole S 80° W 88.63'
S 1/4 cor. Sec. 36, 7-12 N 90° W 34.14'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/21/94


CHAIRMAN *Harry K. K.*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 Standard Kent County Monument

N face fiberglass light pole N 79° E 26.70'
N face 8" steel light pole S 10° W 22.58'
E face 12" steel guy pole S 80° W 88.63'
S 1/4 cor. Sec. 36, T7N R12W, N 90° W 35.14'



Signed by *Randy J. Kolehouse*
Surveyor's Michigan License No. 25854

Date 11/21/94