

**SURVEY & REMONUMENTATION**

APR 28 1995

Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 NOV 29 AM 9:25

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Wendell Bond*  
REG. OF DEEDS

For corners in  
Kent

(County)

Located In:

Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>6N</u> R <u>12W</u> | <u>L-3</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

7495

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on April 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-3	1831	G.L.O. Notes	L. Lyon	Set Post
	1931	Survey Records	City of Grand Rapids	City Iron
	1984	L.C.R.C. #3925	Rosema	Fnd. City Iron in Mon. Box/Set K.C. Mon.
	1988	L.C.R.C. #4710	Bueche	K.C. Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by Maurice J. Rosema on 8/14/84 and was recorded per L.C.R.C. #3925.

P.A. 345 1980 KENT COUNTY  
PEER APPROVED 12/11/94  
CHAIRMAN *Randy Kolehouse*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-3 Found K.C. Monument at C/L of Burton Street running E-W per L.C.R.C.'s #3925 and #4710 as set by M. Rosema in place of a square iron (City) in monument box which he found and checked with City of Grand Rapids survey records.

L.C.R.C. #4710

L.C.R.C. #3925

Nail & remon. tag-SW side power & light pole N 10° W 22.18'	Face of 0.4' dia. steel post (grd. level) S 55° W 59.96'
Face of .4' dia. steel post (grd. level) S 55° W 59.96'	SW cor. conc. block fndn. of house N 45° E 65.65'
SW cor. conc. block fndn. of house N 45° E 65.65'	SE cor. conc. fndn. of porch N 65° W 106.74'
SE cor. conc. fndn. of porch N 65° W 106.74'	KC remon. tag & nail SW side power & light pole N 10° W 22.18'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- L-3 Standard Kent County Monument
- Face of 0.4' dia. steel post (grd. level) S 55° W 59.96'
  - SW cor. conc. block fndn. of house N 45° E 65.65'
  - SE cor. conc. fndn. of porch N 65° W 106.74'
  - Nail & K.C. remon. tag-SW side power & light pole N 10° W 22.18'
  - Nail & K.C. remon tag-W side 8" pine S 12° E 43.97'



Signed by *Randy J. Kolehouse*  
Surveyor's Michigan License No. 25854

Date 11/21/94