

**SURVEY &  
REMONUMENTATION**

APR 28 1995

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

DEC -6 AM 8:59

For corners in **COMMISSION**

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>L-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*W. J. Bond*  
REG. OF DEEDS

7756

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on November 7 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-4 This corner was not originally set by the G.L.O.

1916	Survey Records	Williams & Works	Stone
1921-1957	Survey Records	Williams & Works	City Iron
1930	Survey Records	City of Grand Rapids	City Iron
1957	Survey Records	Williams & Works	3/4" Iron
1973	L.C.R.C. #503	Williams & Works	1" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


L-4 Found 1" iron per L.C.R.C. #503 which checks Williams & Works and the City of Grand Rapids survey records back to the location of the stone shown by Williams & Works in 1916. Iron is 11.8' South and 5.9' West of the intersection of 1/4 line. Accepted iron as Center of Section.

P.A. 343 1988 KENT COUNTY  
PEER APPROVED 11/17/99  
CHAIRMAN *Harry Hubbard*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-4 Replaced 1" iron with a Standard 4" x 30" Kent County Monument.

- Nail & tag in N side 28" Oak S 85° E 84.50'
- Nail & K.C. remon. tag in S side 10" Oak S 40° E 16.95'
- Nail & K.C. remon. tag in NE side 12" Oak S 20° E 24.16'
- Nail & K.C. remon. tag in NW side 12" Oak S 85° W 42.47'



Signed by Randy Kolehouse  
Surveyor's Michigan License No. 25854

Date 12/1/99