

SURVEY & REMONUMENTATION

Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 29 AM 9:25

For corners in **COMMISSION**
Kent

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

W. J. Kolehhouse
REG. OF DEEDS

7499

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehhouse, in a field survey on April 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11	1831	G.L.O. Notes	L. Lyon	Set Post
	1972	L.C.R.C. #244	Williams & Works	"T" Iron Fen. Post
	1972	L.C.R.C. #276	Medema Van Kooten	"T" Fen. Post
	1981	L.C.R.C. #1825	Exxel Engineering	"T" Fen. Post/ 3/4"
	1988	L.C.R.C. #4714	Bueche	K.C. Mon.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/28/94
CHAIRMAN [Signature]
Iron/Set K.C. Mon.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering, Inc., on 9/2/81 and was recorded per L.C.R.C. #1825.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Found K.C. Monument 7' + E of the C/L of Ely Set of R.R. tracks per L.C.R.C.'s #1825 and #4714 which was set by Exxel Engineering in place of a "T" fence post over a 3/4" iron they found which checked L.C.R.C.'s #244 and #276.

L.C.R.C. #1825

C/L E'ly RR tracks W 7.06'
Nail & K.C. remon. tag in N'ly side 36" Oak (2' high) N 75° E 33.71'
Nail & K.C. remon. tag in SE'ly side 16" Oak (1' high) N 45° E 53.10'
Conc. plat mon. E 25.60'


L.C.R.C. #4714

C/L E'ly RR tracks W 7.06'
P.K. nail & K.C. remon tag in C/L W'ly RR tracks W 24.88'
Nail & K.C. remon. tag in N'ly side 36" Oak (2' high) N 75° E 33.71'
Nail & K.C. remon. tag in SE'ly side 16" Oak (1' high) N 45° E 53.10'
Conc. plat mon. E 25.60'
Mon. is in gravel shoulder of RR tracks

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Standard Kent County Monument
C/L E'ly RR tracks W 7.06'
P.K. nail & K.C. remon tag in C/L W'ly RR tracks W 24.88'
Nail & K.C. remon. tag in N'ly side 36" Oak (2' high) N 75° E 33.71'
Nail & K.C. remon. tag in SE'ly side 16" Oak (1' high) N 45° E 53.10'
Conc. plat mon. E 25.60'
Nail & K.C. remon. tag in SW'ly side 15" Oak (1' high) N 4° W 102.58'



Signed by Randy J. Kolehhouse
Surveyor's Michigan License No. 25854

Date 11/21/94