

# SURVEY & REMONUMENTATION

Kent County Remonumentation

APR 28 1995

## LAND CORNER RECORDATION CERTIFICATE COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 NOV 29 AM 9:25

For corners in  
Kent

(County)

Located In:

Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>6N</u> R <u>12W</u> | <u>M-1</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

*Tim J. Bond*  
REG. OF DEEDS

7501

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Randy Kolehouse, in a field survey on July 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-1	1831	G.L.O. Notes	L. Lyon	Set Post	P.A. 345 1900 KENT COUNTY
	N/A	Survey Notes	Williams & Works	City Iron	PEER APPROVED <u>11/11/94</u>
	N/A	Survey Notes	City of Grand Rapids	City Iron	CHAIRMAN <u>Henry Fisher</u>
	1982	L.C.R.C. #2933	Exxel Engineering	P.K. Nail	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group and monumented by William R. Byl on 11/30/84 and was recorded per L.C.R.C. #4042.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-1 Found 1/2" iron with K.C. cap on C/L of Hall Street E-W and C/L Division Avenue North per L.C.R.C. #2933 as set by William Byl in place of a P.K. nail he found which checked L.C.R.C. #2933 and ties to C/L of Division Avenue.

L.C.R.C. #4042


- Nail & tag E side traffic signal pole S 45° E 56.86'
- Nail & tag N side traffic signal pole N 45° W 51.91'
- SW cor. brick veneer of bldg. N 55° E 75.45'
- NW cor. fndn. bldg. S 15° E 118.15'
- NE cor. fndn. bldg. S 45° W 44.79'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-1 Standard Kent County Monument

- Nail & K.C. remon. tag-E side traffic signal pole S 45° E 56.86'
- Nail & K.C. remon. tag-N side traffic signal pole N 45° W 51.91'
- SW cor. brick veneer of bldg. N 55° E 75.45'
- NW cor. fndn. bldg. S 15° E 118.15'
- NE cor. fndn. bldg. S 45° W 44.79'



Signed by Randy J. Kolehouse  
Surveyor's Michigan License No. 25854

Date 11/21/94