

**SURVEY & REMONUMENTATION**

Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

94 NOV 29 AM 9:25

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kent

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>12W</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Tim J. Ford*  
REG. OF DEEDS

7503

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on July 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-3	1831	G.L.O. Notes	L. Lyon	Set Post
	1910-1950	Survey Records	Williams & Works	City Iron
	1931	Survey Records	City of Grand Rapids	City Iron
	1984	L.C.R.C. #3901	William Byl	Fnd. City Iron in M.B./Set K.C. Mon.
	1988	L.C.R.C. #4717	Bueche	K.C. Mon.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 8/11/94  
CHAIRMAN Henry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group monumented by William R. Byl on 4/9/84 and was recorded per L.C.R.C. #3901.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 Found K.C. Monument in C/L of Division Avenue N-S and Burton Stret E-W per L.C.R.C.'s #3901 and #4717 as set by William Byl in place of a City Iron he found in a monument box which checked Williams & Works and City City of Grand Rapids survey records.

L.C.R.C. #4717

L.C.R.C. #3901


Marble face of bldg. corner N 50° W 52.30'  
NE corner of fndn. of bank bldg. S 53° W 50.08'  
"X"-conc. base of sign pole N 50° E 54.26'  
K.C. mon. (NW cor. Sec. 7, 6-11) S 00° W 19.84'

Marble face of bldg. corner N 50° W 52.30'  
K.C. mon. (NW cor. Sec. 7, 6-11) S 00° W 19.84'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 Standard Kent County Monument  
Marble face of bldg. corner N 50° W 52.30'  
NE corner of fndn. of bank bldg. S 53° W 50.08'  
"X"-conc. base of sign pole N 50° E 54.26'  
"X"-conc. base S 25° E 84.90'  
Kent County Monument (NW cor. Sec. 7, 6-11) S 00° W 19.84'



Signed by Randy J. Kolehouse  
Surveyor's Michigan License No. 25854

Date 11/21/94