

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

SECTION

<u>Kent</u> (County)	Located in: Vergennes Township	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>9W</u>	<u>A-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REG. OF DEEDS

Lucy Spauld

97 NOV 14 AM 9:00

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10288

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on June 3 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6	1831	G.L.O. Notes	Mullett	Set Post
		Witness Map	K.C. Surveyor	1-1/4" Iron
	1972	L.C.R.C. #465	Williams & Works	"T" Iron (M-6, T7N, R10W)
	1981	L.C.R.C. #1917	Jonker Land Surveys	Fnd. "T" Iron / Set K.C. Monument (M-6, T7N, R10W)
	1991	L.C.R.C. #5822	Exxel Engineering	K.C. Monument
	1994	L.C.R.C. #8051	Glaza & Associates	K.C. Monument (M-6, T7N, R10W)

Note: This corner is common with M-6, T7N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 7/17/81 and was recorded per L.C.R.C. #1917.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 Found a Standard Kent County Monument (.4' below grade) 4' South of the C/L of Downes Road (gravel) running East and West and 125' East of the C/L of Kelly Lane Pvt. (gravel) per L.C.R.C.'s #1917, #5822 and #8051 as set by Rob Jonker in place of a "T" iron he found along side of a bent 1-1/2" x 10" pipe which checked L.C.R.C. #465 and the K.C. Surveyor's records.

L.C.R.C. #1917

L.C.R.C. #8051

Remon. tag on E. side 16" Oak N 40° E 32.65'	Nail & K.C. remon tag in E side 24" Oak N 42° E 32.65'
Remon. tag on N side 26" Oak N 79° E 77.50'	Nail & K.C. remon tag in N side 28" Oak N 80° E 77.56'
Remon. tag on W side 18" Dbl. Hickory S 01° W 18.00'	Nail & K.C. remon tag in W side 20" Dbl. Hickory S 07° W 18.23'
Remon. tag on S side 26" Oak N 63° W 72.28'	Nail & K.C. remon tag in S side 28" Oak N 64° W 72.23'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 Standard Kent County Monument P.A. 345 1990 KENT COUNTY

- Nail & K.C. remon. tag on E side 24" Oak N 42° E 32.65'
- Nail & K.C. remon. tag on N side 28" Oak N 80° E 77.56'
- Nail & K.C. remon. tag on W side 20" Dbl. Oak S 07° W 18.23'
- Nail & K.C. remon. tag on S side 28" Oak N 64° W 72.23'

PEER APPROVED 8/23/97
CHAIRMAN Randy Kolehouse

Signed by *Randy J. Kolehouse* Date 9/23/97
EARTH TECH

Surveyor's Michigan License No. 25854

